



Webinar | Sep 10, 2019

BrIM Applications on the Signature Wekiva Parkway Segmental Bridge

Jerry Pfuntner, P.E. S.E. | Ivan Liu, P.E. |
Andrés von Breymann



Agenda

- + Introduction to the Wekiva Parkway Project
- + Why use BrIM?
- + Construction sequencing and details
- + SOFiSTiK modeling for the design and construction engineering
- + BrIM applications during design, construction, and drawing production
- + Technical bridge innovations
- + Lessons Learned
- + Questions / Discussion




Photo courtesy of Superior Construction.



Wekiva Parkway Signature Segmental Bridge (Section 6)

WEKIVA PARKWAY SECTION 6 (SR 429) FPID:238275-7-52-01 FROM STATE ROAD (SR) 429 TO JUST WEST OF LONGWOOD-MARKHAM ROAD



Wekiva Parkway Signature Segmental Bridge (Section 6)

Client: Florida Department of Transportation District 5, National Park Service

Contractor: Superior Construction Company

Prime Consultant: WGI


Segmental Bridge Design & Construction Engineering: FINLEY Engineering Group, Inc.


Photo courtesy of Superior Construction.





Why use BrIM??

- + Integration of both design and construction drawings and details
- + Enhanced visualization of complex details with 3D graphics, colors, etc.
- + Enhanced Quality Control







NOTES:


1. ALL SPAN AND SEGMENT LENGTHS ARE MEASURED ALONG THE € BOX GIRDER.
2. WORK THIS SHEET WITH "TYPICAL SEGMENT DIMENSIONS (NORTHBOUND AND SOUTHBOUND)" AND "TYPICAL SEGMENT DIMENSIONS (SERVICE ROAD 1)" SHEETS.
3. FOR MAINTENANCE LIGHTING REQUIREMENTS REFERENCE STANDARD INDEX NO. 21240, BOX GIRDER MAINTENANCE

LEGEND:

- | | |
|--------------------------|--------------------|
| D1 = DEVIATOR (TYPE 1) | CP = CLOSURE POUR |
| D2 = DEVIATOR (TYPE 2) | V = VENT HOLE |
| TB = TOP ANCHOR BLOCK | A = ACCESS OPENING |
| BB = BOTTOM ANCHOR BLOCK | |

Photo courtesy of Superior Construction.






NOTE:

- FOR SEGMENT LENGTHS, JOINT NUMBERS, AND VENT HOLE LOCATIONS SEE "SEGMENT LAYOUT" SHEETS.

SECTION	DIM "A"	DIM "B"	DIM "C"
1A	16'-8 $\frac{3}{8}$ "	2'-5 $\frac{1}{8}$ "	22'-11 $\frac{1}{4}$ "
2A	15'-3"	2'-1 $\frac{1}{8}$ "	23'-1"
3A	13'-1 $\frac{1}{4}$ "	1'-10 $\frac{1}{8}$ "	23'-1 $\frac{1}{2}$ "
4A	12'-9 $\frac{3}{8}$ "	1'-7 $\frac{1}{8}$ "	24'-8 $\frac{3}{4}$ "
5A	11'-9 $\frac{3}{8}$ "	1'-4 $\frac{1}{8}$ "	25'-4 $\frac{3}{4}$ "
6A	10'-11 $\frac{1}{8}$ "	1'-2 $\frac{1}{8}$ "	25'-11 $\frac{1}{8}$ "
7A	10'-2 $\frac{1}{8}$ "	1'-0 $\frac{1}{8}$ "	26'-5 $\frac{1}{8}$ "
8A	9'-8 $\frac{3}{8}$ "	0'-10 $\frac{1}{8}$ "	26'-9 $\frac{1}{2}$ "
9A	9'-3 $\frac{1}{4}$ "	0'-9 $\frac{1}{8}$ "	27'-0 $\frac{3}{4}$ "
10A	9'-0 $\frac{1}{8}$ "	0'-9 $\frac{1}{4}$ "	27'-2 $\frac{3}{8}$ "
11A	9'-0"	0'-9"	27'-3"
1B	17'-4 $\frac{3}{8}$ "	2'-7 $\frac{1}{8}$ "	21'-8"
2B	15'-9 $\frac{1}{2}$ "	2'-3 $\frac{1}{8}$ "	22'-8 $\frac{3}{4}$ "
3B	14'-4 $\frac{3}{8}$ "	1'-11 $\frac{3}{8}$ "	23'-8 $\frac{3}{8}$ "
4B	13'-1 $\frac{1}{4}$ "	1'-8"	24'-6 $\frac{1}{8}$ "
5B	12'-0 $\frac{1}{4}$ "	1'-5"	25'-2 $\frac{1}{8}$ "
6B	11'-1 $\frac{1}{8}$ "	1'-2 $\frac{1}{8}$ "	25'-10 $\frac{1}{4}$ "
7B	10'-4 $\frac{1}{8}$ "	1'-0 $\frac{1}{8}$ "	26'-4 $\frac{1}{4}$ "
8B	9'-9"	0'-11"	26'-9"
9B	9'-4"	0'-9 $\frac{1}{8}$ "	27'-0 $\frac{3}{8}$ "
10B	9'-1"	0'-9 $\frac{1}{4}$ "	27'-2 $\frac{3}{8}$ "
11B	9'-0"	0'-9"	27'-3"


HALF CROSS-SECTION (PIER)

HALF CROSS-SECTION (MIDSPAN)



VENT HOLE NOTES:

- FORM VENT HOLE WITH PERMANENT PVC WITH UV INHIBITOR PIPE.
- VERMIN GUARD SHALL BE 20 GAGE GALVANIZED WELDED METAL SCREEN WITH $\frac{1}{4}$ " OPENING. FASTEN VERMIN GUARDS TO TOP OF BOTTOM SLAB WITH "EPOXY FOR STRUCTURAL APPLICATIONS" IN ACCORDANCE WITH "FDOT STANDARD SPECIFICATIONS SECTION 937".





NOTE:

1. SEE "TYPICAL SEGMENT DIMENSIONS" SHEET FOR SEGMENT DIMENSIONS.

Photo courtesy of Superior Construction.







LEGEND

- ▶ = STRESSING ANCHOR
- ▽ = NON-STRESSING ANCHOR
- B = BOTTOM CONTINUITY TENDONS
- P = PROVISIONAL PT DUCT

NOTES:

1. FOR POST-TENSIONING SYSTEM, SEE "POST-TENSIONING QUANTITIES AND STRESSING SCHEDULE" SHEETS.
2. FOR ALL SECTIONS, SEE "LONGITUDINAL POST TENSIONING DETAILS (3 OF 4) AND (4 OF 4)" SHEETS.




NOTES:

1. FOR TENDON SIZE AND POST-TENSIONING SYSTEM, SEE "POST-TENSIONING QUANTITIES AND STRESSING SCHEDULE" SHEETS.
2. FOR ALL SECTIONS, SEE "LONGITUDINAL POST TENSIONING DETAILS (3 OF 4) AND (4 OF 4)" SHEETS.

What are flexible fillers?

- + Microcrystalline wax
- + Provides strand protection
- + Enable tendon strand replacement
- + Provides zero bond of the strand to the surrounding concrete



- + Current Code does not provide for 'hinge' locations for internal unbonded tendons
- + Experimental tests show localized crack distribution

Ref. Brenkus UF Ph.D. dissertation




Figure 8-7. 30 degree cone of influence

+ Wekiva continuity tendon design

~~$$f_{ps} = f_{pc} + 900 \left(\frac{d_p - e}{l_e} \right) \leq f_{py}$$~~

in which:


$$l_e = \left(\frac{2l_i}{2 + N_s} \right)$$

BrIM = Bridge *Integration* Modeling

Phase 1 → Input of Global CAD Geometry


Phase 2 → Development of Models

Phase 3 → Generation of Integrated Model




Global CAD Geometry

Horizontal Alignment					
	X	Y	DX	DY	Station
Start point	496168.328	148408.795	182.201	88.000	254300.000
Type	Subtype	Length	R	Ra	Re
Straight line	-	202.339	x	x	x
Circular arc	-	54.940	-13759.240	x	x
Circular arc	-	150.640	-10007.000	x	x
Circular arc	-	54.970	-13759.240	x	x
Straight line	-	344.459	x	x	x
Circular arc	-	60.020	9798.360	x	x
Circular arc	-	40.060	4515.150	x	x
Circular arc	-	194.500	4007.000	x	x
Circular arc	-	40.070	4515.150	x	x
Circular arc	-	60.040	9798.360	x	x
Straight line	-	202.410	x	x	x
Circular arc	-	40.020	-21881.800	x	x
Circular arc	-	39.960	-7066.080	x	x
Circular arc	-	224.620	-6007.000	x	x
Circular arc	-	39.960	-7066.080	x	x
Circular arc	-	39.990	-21881.800	x	x
Straight line	-	111.000	x	x	x




SOFISTIK Export												
Unit set: 8												
[SOFISTIK standard = 0 - Standard units, 8 - Imperial units]												
Section	Material	Zerpoint [°EDGE° PLINE]										
1	1	0										
PT data												
PT no	PT name	NOPS	nu	CS	const	CSE	cons	LC	load	(Stressing Force	Slip	CS-grout
1015	C2-1-LEFT	1	1005	0	701	0	485	0.03125	1015			
1035	C2-2-LEFT	1	1015	0	702	1	485	0.03125	1035			
1055	C2-3-LEFT	1	1035	0	703	0	485	0.03125	1065			
1075	C2-4-LEFT	1	1065	0	704	1	485	0.03125	1085			
1095	C2-5-LEFT	1	1085	0	705	0	485	0.03125	1115			
1115	C2-6-LEFT	1	1115	0	706	1	485	0.03125	1135			
1135	C2-7-LEFT	1	1135	0	707	0	485	0.03125	1165			
1155	C2-8-LEFT	1	1165	0	708	1	485	0.03125	1185			
1175	C2-9-LEFT	1	1185	0	709	0	485	0.03125	1215			
1195	C2-10-LEFT	1	1215	0	710	1	485	0.03125	1235			
1215	C2-11-LEFT	1	1235	0	711	0	485	0.03125	1265			
1235	C2-12-LEFT	1	1265	0	712	1	485	0.03125	1285			
1255	C2-13-LEFT	1	1285	0	713	0	485	0.03125	1315			
1275	C2-14-LEFT	1	1315	0	714	1	485	0.03125	1335			
1295	C2-15-LEFT	1	1335	0	715	0	485	0.03125	1365			

SOFiSTiK Analysis Modeling



SOFiPlus Interface



Load Creation

```

$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$
$ CANTILEVER FORM TRAVELLER LOADS $
$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$$

$$ UPSTATION TRAVELLER LOADS

$LET#TRAV_P 0 $ KIP FORM TRAVELLER WEIGHT

$LET#TRAV_M 0 $ KIP*FT FORM TRAVELLER COG ECCENTRICITY FROM BH FACE MOMENT

LET#TRAV_P 172 $ KIP FORM TRAVELLER WEIGHT

LET#TRAV_M 1011 $ KIP*FT FORM TRAVELLER COG ECCENTRICITY FROM BH FACE MOMENT

LET#I 0

LOOP #N_CANT
LET#J 0

LOOP #N_UP(#SEQ(#I)-1) $has been modified since the Design Phase

  LC #N(#I)*1000+(2*#J+1)*10+1 TYPE 'D_1' TITL 'FORM TRAVELLER'
  BEPL FROM GRP #SEQ(#I)*100+(2*#J+1) TYPE PG P #TRAV_P
  BEPL FROM GRP #SEQ(#I)*100+(2*#J+1) TYPE MY P -1*#TRAV_M

  LET#J #J+1
ENDLOOP

if #N_UP(#SEQ(#I)-1)==10


LET#J #N_UP(#SEQ(#I)-1)-1 $final traveler advancement

  LC #N(#I)*1000+(2*(#J+1)+1)*10+1 TYPE 'D_1' TITL 'FORM TRAVELLER_final_advancement'
  BEPL FROM GRP #SEQ(#I)*100+(2*#J+1) TYPE PG P #TRAV_P A 16
  BEPL FROM GRP #SEQ(#I)*100+(2*#J+1) TYPE MY P -1*#TRAV_M A 16
ENDIF

LET#I #I+1
ENDLOOP

$$ DOWNSTATION TRAVELLER LOADS

```



Integrated 3D Bridge Model




STEP 6A:
SPAN 7 AND SPAN 9 ENDSpan UNITS MAY BE CAST AT THIS TIME.

NOTE: REFER TO TABLES ON THIS SHEET FOR [N] AND [X] VALUES.

STEP 6B: (REPEAT THIS STEP FOR SEGMENTS 8-3U TO 8-9D & 9-3D TO 9-9U)

1. ADVANCE FORM TRAVELERS AT SEGMENTS 8-[N-2]U & 9-[N-2]D IN POSITION TO CAST SEGMENTS 8-[N]U & 9-[N]D.
2. CAST SEGMENTS 8-[N]U & 9-[N]D PER GENERAL PROCEDURE SHEET "CM-GT".
3. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI, INSTALL AND STRESS TRANSVERSE TENDONS, PT BARS, AND CANTILEVER TENDONS C(X) IN ANY ORDER AS PER PT STRESSING DATA.
4. GROUT TENDONS AND POUR BACK BLOCKOUTS.
5. ADVANCE FORM TRAVELERS AT SEGMENTS 8-[N-2]D & 9-[N-2]U IN POSITION TO CAST SEGMENTS 8-[N]D & 9-[N]U.
6. CAST SEGMENTS 8-[N]D & 9-[N]U PER GENERAL PROCEDURE SHEET "CM-GT".
7. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI, INSTALL AND STRESS TRANSVERSE TENDONS, PT BARS, AND CANTILEVER TENDONS C(X) IN ANY ORDER AS PER PT STRESSING DATA.
8. GROUT TENDONS AND POUR BACK BLOCKOUTS.




TRANSITION PIER 7

STEP 3:


1. CONSTRUCT PIER TABLE FORMWORK.
2. CAST PIER TABLE AT PIERS 8 & 9 ON FALSEWORK.
3. ONCE PIER TABLE CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
4. ONCE PIER TABLE CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C1 IN ANY ORDER AS PER PT STRESSING DATA.
5. GROUT TENDONS AND POUR BACK BLOCKOUTS.*

* THIS STEP MAY BE COMPLETED AT ANY TIME WITHIN THE TIME FRAME ALLOWED BY THE SPECIFICATIONS.

DIRECTION OF STATIONING →




MAINSPAN PIER 8




MAINSPAN PIER 9

← DIRECTION OF STATIONING



TRANSITION PIER 10



Pier Table Falsework





Photo courtesy of Superior Construction.



Photos courtesy of Superior Construction.



Pier Table Segment Model



- STEP 4:**
1. DISASSEMBLE AND REMOVE PIER TABLE FALSEWORK AT PIERS 8 & 9.
 2. STRESS THE TRANSVERSE DIAPHRAGM TENDONS AT ALTERNATING ENDS.*
 3. ERECT FORM TRAVELERS IN POSITION TO CAST SEGMENTS 8-1D/8-1U & 9-1D/9-1U.
 4. CAST SEGMENTS 8-1U & 9-1D PER GENERAL PROCEDURE SHEET "CM-G1".**
 5. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
 6. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C2 IN ANY ORDER AS PER PT STRESSING DATA.
 7. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 4250PSI, FORM TRAVELERS AT 8-1U AND 9-1D MAY BE ADVANCED.
 8. GROUT TENDONS AND POUR BACK BLOCKOUTS.***
 9. CAST SEGMENTS 8-1D & 9-1U PER GENERAL PROCEDURE SHEET "CM-G1".**
 10. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
 11. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C3 IN ANY ORDER AS PER PT STRESSING DATA.
 12. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 4250PSI, FORM TRAVELERS AT 8-1D AND 9-1U MAY BE ADVANCED.
 13. GROUT TENDONS AND POUR BACK BLOCKOUTS.***
- * AT THE CONTRACTOR'S OPTION, ALL TRANSVERSE DIAPHRAGM TENDONS MAY BE DISCARDED AND RESTRESSED TO COMPLY WITH THE TIME FRAME ALLOWED BY THE SPECIFICATIONS TO COMPLETE THE FLEXIBLE FILLER INJECTION. THE TENDONS MAY BE DESTRESSED PER THE FOLLOWING SEQUENCE (THIS STEP MUST BE COMPLETED PRIOR TO THE FORM TRAVELER LOAD TEST OPERATION):
- PIER 8 DIAPHRAGM TENDONS: AFTER CLOSURE TENDONS STRESSED IN SPAN 7
 - PIER 9 DIAPHRAGM TENDONS: AFTER CLOSURE TENDONS STRESSED IN SPAN 9
- ** CONSTRUCTION OF CANTILEVER 8 AND 9 MAY BE CONDUCTED INDEPENDENTLY.
- *** THIS STEP MAY BE COMPLETED AT ANY TIME WITHIN THE TIME FRAME ALLOWED BY THE SPECIFICATIONS.





Photo courtesy of Superior Construction.



Photos courtesy of Superior Construction.




Photos courtesy of Superior Construction.




Photos courtesy of Superior Construction.



Typical Segment Model





REINFORCEMENT QUANTITIES																						
BARMARK	DESCRIPTION	ITEM QTY	SIZE	TYPE	LENGTH	A	B	C	D	E	F	G	H	I	J	K	L	N	O	R	DIM LIMIT	TOTAL LBS
4TS01a	Bottom Slab Bott	1	#4	13	27'-8 3/4"		26'-6"	8"	8"									71.57	71.57			18.5
4TS01b	Bottom Slab Bott	1	#4	13	27'-8 1/2"		26'-6"	8"	8"									71.57	71.57			18.5
4TS01c	Bottom Slab Bott	1	#4	13	27'-8 1/4"		26'-5 3/4"	8"	8"									71.57	71.57			18.5
4TS01d	Bottom Slab Bott	1	#4	13	27'-8"		26'-5 1/4"	8"	8"									71.57	71.57			18.5
4TS01e	Bottom Slab Bott	1	#4	13	27'-7 3/4"		26'-5 1/4"	8"	8"									71.57	71.57			18.5
4TS01f	Bottom Slab Bott	1	#4	13	27'-7 1/2"		26'-5"	8"	8"									71.57	71.57			18.5
4TS01g	Bottom Slab Bott	1	#4	13	27'-7 1/4"		26'-4 3/4"	8"	8"									71.57	71.57			18.4
4TS01h	Bottom Slab Bott	1	#4	13	27'-7"		26'-4 1/2"	8"	8"									71.57	71.57			18.4
4TS01i	Bottom Slab Bott	1	#4	13	27'-7"		26'-4 1/4"	8"	8"									71.57	71.57			18.4
4TS01j	Bottom Slab Bott	1	#4	13	27'-6 3/4"		26'-4"	8"	8"									71.57	71.57			18.4
4TS01k	Bottom Slab Bott	1	#4	13	27'-6 1/2"		26'-3 3/4"	8"	8"									71.57	71.57			18.4
4TS01l	Bottom Slab Bott	1	#4	13	27'-6 1/4"		26'-3 1/2"	8"	8"									71.57	71.57			18.4
4TS01m	Bottom Slab Bott	1	#4	13	27'-6"		26'-3 1/4"	8"	8"									71.57	71.57			18.4
4TS01n	Bottom Slab Bott	1	#4	13	27'-5 3/4"		26'-3 1/4"	8"	8"									71.57	71.57			18.4
4TS01o	Bottom Slab Bott	1	#4	13	27'-5 1/2"		26'-3"	8"	8"									71.57	71.57			18.3
4TS01p	Bottom Slab Bott	1	#4	13	27'-5 1/4"		26'-2 3/4"	8"	8"									71.57	71.57			18.3
4TS01q	Bottom Slab Bott	1	#4	13	27'-5"		26'-2 1/2"	8"	8"									71.57	71.57			18.3
4TS01r	Bottom Slab Bott	1	#4	13	27'-4 3/4"		26'-2 1/4"	8"	8"									71.57	71.57			18.3
4TS02s	Bottom Slab Top	1	#4	13	27'-10 3/4"		26'-8 1/4"	8"	8"									71.57	71.57			18.6
4TS02t	Bottom Slab Top	1	#4	13	27'-10 1/2"		26'-8"	8"	8"									71.57	71.57			18.6
4TS02u	Bottom Slab Top	1	#4	13	27'-10 1/2"		26'-7 3/4"	8"	8"									71.57	71.57			18.6
4TS02v	Bottom Slab Top	1	#4	13	27'-10 1/4"		26'-7 1/2"	8"	8"									71.57	71.57			18.6
4TS02w	Bottom Slab Top	1	#4	13	27'-10"		26'-7 1/2"	8"	8"									71.57	71.57			18.6
4TS02x	Bottom Slab Top	1	#4	13	27'-9 3/4"		26'-7 1/4"	8"	8"									71.57	71.57			18.6
4TS03	Bottom Slab Haunch	40	#4	12	8'-7 1/2"		8'-0"	8"											64.44			230.5
4TS04	Haunch	48	#4	14	6'-1 1/2"		4'-2 1/4"	2'-4 3/4"											45.00			196.4
4TS05	Top Slab Haunch	48	#4	14	21'-6 1/2"		10'-4"	11'-2 3/4"											155.19			690.7
4TS06	Wing Tip	14	#4	35	10'-7 3/4"		3'-2"	4"	0'-0"	7'-4 1/4"												99.6
4TS08	Top Slab Bott	24	#4	1	14'-7 1/4"		14'-7 1/4"															234.1
4TS09	Longitudinal bar	206	#4	01	18'-4"		18'-4"															2522.8
4TS10	Top Slab Thick End	14	#4	35	10'-9 1/4"		7'-4 1/4"	5 1/2"	1/4"	3'-2"												100.7
4TS11	Bottom Slab Corner	48	#4	15	5'-1 1/2"		2'-8 1/2"	8"	1'-11"									71.57	90.00			164.3

BAR LIST NOTES:

1. ALL BAR BEND DIMENSIONS ARE OUT TO OUT.
2. LENGTH GIVEN IS ACTUAL BAR LENGTH.
3. FOR BAR BENDING DETAILS REFER TO FDOT STANDARD INDEX.
4. DIMENSIONAL LIMITATIONS (DIM LIMIT) DENOTE DIMENSIONS WITH A TOLERANCE OF 0" LONG TO -1" SHORT.
5. REBAR WEIGHTS ARE BASED ON ACTUAL BAR LENGTHS.

SUBMITTAL REVIEW

Approved Approved as Noted
 Rejected Revise and Resubmit



This review is only for general confirmation with the design concept and the information given in the Construction Documents. Corrections or comments made on the shop drawings during this review do not release the Contractor from compliance with the requirements of the plans and specifications and applicable codes. Acceptance of a specific item shall not include acceptance of an assembly of which the item is a component. The Contractor is responsible for dimensions to be confirmed and controlled at the job site. Information that pertains solely to the fabrication process or to the means, methods, techniques, sequences and procedures of construction, coordination of the Work with that of all other trades and performing all Work in a safe and satisfactory manner.

FINLEY ENGINEERING GROUP, INC.

DATE: 06/2018 BY: Jerry Pflunther, P.E.

- STEP 5B:**
1. ADVANCE FORM TRAVELERS AT PIER TABLE IN POSITION TO CAST SEGMENTS 8-2U & 9-2D.
 2. CAST SEGMENTS 8-2U & 9-2D PER GENERAL PROCEDURE SHEET "CM-G1".*
 3. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
 4. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C4 IN ANY ORDER AS PER PT STRESSING DATA.
 5. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 4250PSI, FORM TRAVELERS AT 8-2U AND 9-2D MAY BE ADVANCED.
 6. GROUT TENDONS AND POUR BACK BLOCKOUTS.**
 7. ADVANCE FORM TRAVELERS AT PIER TABLE IN POSITION TO CAST SEGMENTS 8-2D & 9-2U.
 8. CAST SEGMENTS 8-2D & 9-2U PER GENERAL PROCEDURE SHEET "CM-G1".*
 9. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
 10. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C5 IN ANY ORDER AS PER PT STRESSING DATA.
 11. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 4250PSI, FORM TRAVELERS AT 8-2D & 9-2U MAY BE ADVANCED.
 12. GROUT TENDONS AND POUR BACK BLOCKOUTS.**

SEGMENT 8-1D




DIRECTION OF STATIONING →

DIRECTION OF STATIONING →

SEGMENT 8-2U

End Span Falsework






Photos courtesy of Superior Construction.



STEP 9:


1. ADVANCE PIER 8 UPSTATION FORM TRAVELER AT SEGMENT 8-8U IN POSITION TO CAST SEGMENT 8-10U.
2. CAST SEGMENT 8-10U PER GENERAL PROCEDURE SHEET "CM-GT".*
3. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
4. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C20 IN ANY ORDER AS PER PT STRESSING DATA.
5. GROUT TENDONS AND POUR BACK BLOCKOUTS.**
6. ADVANCE PIER 8 DOWNSTATION FORM TRAVELER AT SEGMENT 8-8D IN POSITION TO CAST SEGMENT 8-10D.
7. CAST SEGMENT 8-10D PER GENERAL PROCEDURE SHEET "CM-GT".*
8. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3000PSI, INSTALL AND STRESS 4 OF 4 STRANDS FOR EACH TRANSVERSE TENDON AS PER PT STRESSING DATA.
9. ONCE SEGMENT CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 3500PSI STRESS THE CANTILEVER TENDONS C21 IN ANY ORDER AS PER PT STRESSING DATA.
10. GROUT TENDONS AND POUR BACK BLOCKOUTS.**
11. PIER 8 DOWNSTATION FORM TRAVELER MAY BE REMOVED AT THIS TIME.
12. ONCE SEGMENT 8-10U CONCRETE REACHES A MINIMUM COMPRESSIVE STRENGTH OF 4250PSI ADVANCE PIER 8 UPSTATION FORM TRAVELER AT SEGMENT 8-9U IN POSITION TO CAST SPAN 8 CLOSURE SEGMENT. DO NOT ENGAGE FORM TRAVELER ONTO PIER 9 DOWNSTATION CANTILEVER.

NOTE: STEP 13 AND STEP 14 MAY BE PERFORMED SIMULTANEOUSLY.
 * CONSTRUCTION OF CANTILEVER 8 AND 9 MAY BE CONDUCTED INDEPENDENTLY.
 ** THIS STEP MAY BE COMPLETED AT ANY TIME WITHIN THE TIME FRAME ALLOWED BY THE SPECIFICATIONS.



A

Closure Pour Formwork



Technical Bridge Innovations

- + Use of single geometry source to integrate design modelling and construction engineering
- + Ultimate moment resistance design of unbonded internal continuity tendon, unbonded external continuity tendons and bonded mild reinforcement
- + Use of BrIM modelling throughout the design and construction process

Lessons Learned

- + Remember that the precision of 3D modelling does not continue out into the field.... Allow for construction tolerances
- + Quality Control with BrIM modelling requires new processes
- + “Drawings“ from BrIM models do not have to look like traditional 2D plans – use colors, ISO views, etc. to help visualize the details

Photo courtesy of Superior Construction.



Come see the Wekiva Segmental Bridges at the ASBI Convention Bridge Tour!

November 6th, 2019



Photo courtesy of Superior Construction.

Wekiva Parkway Signature Segmental Bridge (Section 6)



Questions?

Jerry Pfuntner, P.E. S.E. | Ivan Liu, P.E. |
Andrés von Breymann